

SECTION 201

CLEARING AND GRUBBING

201.1 GENERAL

This work shall consist of removing natural and man-made objectionable material from the right-of-way, construction areas, road approaches, material and borrow sites, areas through which ditches and channels are to be excavated, and such other areas as may be shown on the plans. Clearing and grubbing shall be performed in advance of grading operations except that in cuts over 3 feet in depth, grubbing may be done simultaneously with excavation, provided stumps, roots, embedded wood, foundations and slabs are removed as specified. Clearing and grubbing shall be in accordance with the requirements herein specified, such as erosion control requirements. Demolition of structures, other than foundations or slabs, shall be as shown on the plans.

201.2 REFERENCES

201.3 PRESERVATION OF PROPERTY

Existing improvements, adjacent property, utility and other facilities, and trees and plants not to be removed shall be protected from injury or damage resulting from the CONTRACTOR's operations. Only trees and plants designated or marked for removal by the ENGINEER shall be removed.

201.4 CONSTRUCTION METHODS

201.4.1 The natural ground surface shall be cleared of vegetable growth, such as trees, tree stumps, logs, roots or downed trees, brush, grass, weeds, and surface boulders, as well as fences, walls, rubbish, foundations and slabs.

201.4.2 Unless otherwise shown on the plans, the entire area of the project within the limit lines specified below shall be cleared and grubbed. No payment will be made to the CONTRACTOR for clearing and grubbing outside these limits, unless such work is authorized by the ENGINEER.

201.5 LIMIT LINES: Except when limit lines for clearing and grubbing are shown on the plans or are staked by the ENGINEER, clearing and grubbing shall extend only within reasonable limits of the work area.

201.6 REMOVAL OF TREES AND TREE BRANCHES

201.6.1 Trees shall be removed in such a manner as not to injure standing trees,

plants, and improvements which are to remain. Tree branches extending over a roadway and which clear finish grade by 12 feet or less shall be cut off close to the boles in a workmanlike manner.

201.6.2 Trees requiring trimming to facilitate normal construction operations shall be trimmed by a tree surgeon.

201.7 REMOVAL AND DISPOSAL OF DEBRIS

Debris to be removed shall be disposed of outside the right-of-way at a location satisfactory to the ENGINEER, except when burning of combustible debris is permitted. The area to be graded and adjacent areas shall be left with a neat and finished appearance. No accumulation of flammable material shall remain on or adjacent to the property line. In case burning precedes construction operations, the piles may be placed in the center of the area; otherwise, the piles shall be placed in the most convenient location at the side of the area and beyond slope lines where they may be burned without damage to surrounding forest cover or adjacent property. Burning shall be done in conformance with local regulations and at such times and in such manner as to prevent the fire from spreading to areas adjoining the construction site. In areas where burning is prohibited by local regulations, all removed material shall be disposed of outside the construction area.

201.8 REMOVAL AND DISPOSAL OF SALVAGEABLE ITEMS

Items and materials of salvage value as shown on the plans or as determined by the ENGINEER, unless incorporated in the new work, shall remain the property of the OWNER and shall be delivered to approved storage areas as directed by the ENGINEER. Such items and materials shall be carefully removed and delivered in such a manner as to permit re-use.

201.9 MEASUREMENT AND PAYMENT

201.9.1 CLEARING AND GRUBBING:

201.9.1.1 When the proposal includes an item for clearing and grubbing, the quantity for measurement shall be as indicated in the Bid Proposal.

201.9.1.2 The unit price per acre paid for clearing and grubbing shall include full compensation for furnishing all labor, materials, tools, equipment, and

incidentals and for doing all the work involved in clearing and grubbing as shown on the plans, as provided in these specifications and as directed by the ENGINEER, including the removal and disposal of resulting material.

201.9.1.3 When the Bid Proposal does not include a pay item for clearing and grubbing as above specified and unless otherwise specified in the Supplementary Specifications, full compensation for any necessary clearing and grubbing required to perform construction operations specified shall be considered as included in the price paid for other items of work and no additional compensation will be allowed therefor.

201.9.2 REMOVAL AND DISPOSAL OF TREES:
If the Bid Proposal includes separate estimates of quantities for the removal of trees, the trees shall be classified by size as follows:

201.9.2.1 Trees less than 12 inches in circumference at 3 feet above the original ground surface shall be considered as included in the price for clearing and grubbing or excavation, and no additional compensation will be allowed therefor.

201.9.2.2 Trees between 12 and 30 inches in circumference shall be measured as a unit price for each tree in the item provided in the Bid Proposal for trees of this dimension.

201.9.2.3 Trees more than 30 inches in circumference shall be measured as a unit price for each tree in the item provided in the Bid Proposal for trees of this dimension.