

SECTION 701

TRENCHING, EXCAVATION AND BACKFILL

701.1 GENERAL

Trench excavation and backfill for underground utilities, sanitary sewer, storm sewer, water lines, and appurtenances shall conform to these specifications or as specified in the Supplemental Technical Specifications or as authorized, in writing, by the ENGINEER.

701.2 REFERENCES

701.2.1 American Society for Testing Materials (Latest Edition)(ASTM)

- D-422 Method for Particle-Size Analysis of Soils
- D-698 Test Method for Moisture-Density Relations of Soils and Soil-Aggregate Mixtures, Using 5.5-lb.(2.49-kg) Rammer and 12-in(304.8-mm) Drop.
- D-1557 Test Method for Moisture-Density Relations of Soils and Soil-Aggregate Mixtures, Using 10-lb.(4.54 kg) Rammer and 18-in(457-mm) Drop.
- D-2321 Recommended Practice for Underground Installation of Flexible Thermoplastic Sewer Pipe
- D-2487 Classification of Soils for Engineering Purposes
- D-2922 Test Method for Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth).
- D-3017 Test Method for Moisture Content of Soil and soil-Aggregate in Place by Nuclear Methods (Shallow Depth)
- D-4318 Test Method for Liquid Limit, Plastic Limit, and Plasticity Index of Soils

701.2.2 This Publication:

- Section 207 Lean Fill Construction
- Section 301 Subgrade Preparation
- Section 302 Aggregate Base Course
- Section 336 Asphalt Concrete Pavement
- Section 337 Portland Cement Concrete Pavement
- Section 340 Portland Cement Concrete Curbs, Gutters, Walks, Driveways, Alley Intersections, and Median Paving

701.3 TERMINOLOGY

701.3.1 For the purpose of these specifications in this Section, the descriptive terms "flexible," "plastic" and "non-rigid" are similarly interchangeable as utilized in these specifications and appurtenant reference material.

701.3.2 Rigid pipe shall be reinforced concrete, concrete cylinder, and vitrified clay pipes.

701.3.3 Flexible pipe shall be polyvinyl chloride, polyethylene, ductile iron, and corrugated metal pipes.

701.3.4 Standard Detail Drawings show the trench cross-sections which identify the meaning and limits of terminology used in these specifications for the terms

"foundation, bedding, haunching, initial backfill, final backfill, embedment, pipe zone, cover, springline, and pipe width."

701.3.5 The Unified Soil Classification System in ASTM D 2487 shall be utilized for the purpose of material classifications. See Table 701.3.A for a listing of referenced soil classes.

701.4 NOTIFICATION OF FORTHCOMING WORK

701.4.1 To assure that the construction work progresses in a timely manner and that good public relations are maintained with the property owners, the following actions are considered essential:

701.4.1.1 Prior to the start of construction the CONTRACTOR shall assist the ENGINEER in notifying the adjacent property owners as to when construction will start, the estimated completion date, who to contact if a problem arises, and any anticipated access blockages.

701.4.1.2 Prior to the start of trenching operations, including pavement cutting and removal, the CONTRACTOR should coordinate with the ENGINEER any problem areas involving traffic control, access to private properties, stockpiling of excavated materials, and other utility conflicts.

701.4.1.3 The CONTRACTOR shall provide the ENGINEER with the name and telephone number of at least two contact persons during non-working hours.

701.5 TRENCH SAFETY

The CONTRACTOR shall be responsible for maintaining all trenches in a safe condition; thereby protecting the workers and the general public. Trench slopes and other protection shall be in accordance with applicable regulations such as the Department of Labor's Occupational Safety and Health Administration Standards 29CFR Part 1926, subpart P or any applicable amendments.

701.6 BRACING EXCAVATIONS

701.6.1 Excavation for pipe shall normally be by open unsupported trenches unless local conditions warrant trench bracing.

701.6.2 Excavations shall be braced and sheeted to provide complete safety to persons working therein and bracing shall comply with applicable Federal (OSHA), State and local laws and ordinances. Support systems for trenches in excess of 20 feet deep and adjacent to existing improvement or subject to vibrations or ground water shall be in accordance with OSHA regulations. The CONTRACTOR shall be fully responsible for sufficiency and adequacy of bracing excavations with

TABLE 701.3.A

EMBEDMENT SOILS CLASSIFICATIONS

SOILS CLASS	SOIL TYPE	DESCRIPTION
CLASS I SOILS*		Manufactured angular, granular material, 1/4 to 1-1/2 inches (6 to 40 mm) size, including materials having regional significance such as crushed stone or rock, broken coral, crushed slag, cinders, or crushed shells, complying to the requirements of Class II soils.
CLASS II SOILS**	GW	Well-graded gravels and gravel-sand mixtures, little or no fines. 50% or more of coarse fraction retained on No. 4 sieve. More than 95% retained on No. 200 sieve. Clean.
CLASS II SOILS**	GP	Poorly graded gravels and gravel-sand mixtures, little or no fines. 50% or more of coarse fraction retained on No. 4 sieve. More than 95% retained on No. 200 sieve. Clean.
CLASS II SOILS **	SW	Well-graded sands and gravelly sands, little or no fines. More than 50% of coarse fraction passes No. 4 sieve. More than 95% retained on No. 200 sieve. Clean.
CLASS II SOILS**	SP	Poorly graded sands and gravelly sands, little or no fines. More than 50% of coarse fraction passes No. 4 sieve. More than 95% retained on No. 200 sieve. Clean.
CLASS III SOILS***	GM	Silty gravels, gravel-sand-silt mixtures. 50% or more of coarse fraction retained on No. 4 sieve. More than 50% retained on No. 200 sieve.
CLASS III SOILS***	GC	Clayey gravels, gravel-sand-clay mixtures. 50% or more of coarse fraction retained on No. 4 sieve. More than 50% retained on No. 200 sieve.
CLASS III SOILS***	SM	Silty sands, sand-silt mixtures. More than 50% of coarse fraction passes No. 4 sieve. More than 50% retained on No. 200 sieve.
CLASS III SOILS***	SC	Clayey sands, sand-clay mixtures. More than 50% of coarse fraction passes No. 4 sieve. More than 50% retained on No. 200 sieve.
CLASS IV SOILS	ML	Inorganic silts, very fine sands, rock flour, silty or clayey fine sands. Liquid limit 50% or less. 50% or more passes No. 200 sieve.
CLASS IV SOILS	CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays. Liquid limit 50% or less. 50% or more passes No. 200 sieve.
CLASS IV SOILS	MH	Inorganic silts, micaceous or diatomaceous fine sands or silts, elastic silts. Liquid limit greater than 50%. 50% or more passes No. 200 sieve.
CLASS IV SOILS	CH	Inorganic clays of high plasticity, fat clays. Liquid limit greater than 50%. 50% or more passes No. 200 sieve.
CLASS V SOILS	OL	Organic silts and organic silty clays or low plasticity. Liquid limit 50% or less. 50% or more passes No. 200 sieve.
CLASS V SOILS	OH	Organic clays of medium to high plasticity. Liquid limit greater than 50%. 50% or more passes No. 200 sieve.
CLASS V SOILS	PT	Peat, muck and other highly organic soils.

* Soils are as defined in ASTM D2487, except for Class I Soil which is defined in ASTM D2321.

** In accordance with ASTM D2487, less than 5% passes No. 200 sieve.

***In accordance with ASTM D2487, soils with 5% to 12% passing No. 200 sieve fall in a borderline classification that is more characteristic of Class II than of Class III.

respect to work under construction and to adjacent utility lines and private property.

701.6.3 If the soil conditions within the trench area require support, the CONTRACTOR may elect to use tight sheeting, skeleton sheeting, stay bracing, trench jacks, or a movable trench shield to support the trench during pipe laying operations, such as: bedding preparation, pipe laying, and backfilling of haunches and initial zone.

701.6.4 No sheeting shall be permitted to remain in the trench except when, in the opinion of the ENGINEER, field conditions or type of sheeting or methods of construction used by the CONTRACTOR, warrant the supports must remain. The ENGINEER may opt to have the lower portion (within the pipe zone) of the sheeting to remain. If the CONTRACTOR plans on removing the sheeting, he shall submit a method to the ENGINEER for approval to treat the void created by the removal of the sheeting within the pipe zone and below.

701.6.5 When a movable trench shield is used, the trailing half of the shield should be notched to the height of the top of the pipe. This will allow the haunch area of the pipe to be compacted properly to the wall of the trench. If the trench shield is not notched, a sub trench shall be excavated for pipe installation such that the bottom of the trench shield does not enter the pipe zone.

701.7 DEWATERING

701.7.1 Trenching and pipe laying operations may encounter standing water or ground water which would preclude the proper placing of bedding, backfilling, and laying pipe. The water shall be removed by pumps and associated equipment, such as well points, to lower the water level. Dewatering shall continue for a minimum of 24 hours after placement of any concrete.

701.7.2 Dewatering operations shall remove the water to achieve a stable foundation for pipe embedment and backfilling. The ENGINEER shall determine if adequate foundation has been attained. The ground water shall be lowered to a minimum depth of 6 inches below pipe grades. Should over excavation be necessary due to unsuitable foundation conditions, the ground water shall be additionally lowered as necessary.

701.7.3 The CONTRACTOR shall submit a plan for approval by the ENGINEER as to how and where the waste water will be disposed. Waste water will not be discharged into traffic and pedestrian lanes or onto private properties.

701.7.4 The CONTRACTOR shall obtain a permit from the New Mexico State Engineer prior to commencing dewatering operations.

701.7.5 The CONTRACTOR shall also be responsible for any adverse effect his dewatering operation has to private

property, including providing temporary water to residences and/or businesses necessitated by the effect on private wells.

701.7.6 The CONTRACTOR shall arrange his dewatering operation in a neat and orderly manner such that access to adjacent properties is maintained, the discharge system does not leak and that any power generation complies with applicable noise limit regulations.

701.8 REMOVAL OF EXISTING PAVEMENT, SIDEWALK, AND DRIVEWAY

701.8.1 Existing concrete pavement, sidewalk, or driveway removed in connection with construction shall be replaced to neatly sawed edges. Cuts shall be neat and to true straight lines with no shatter outside the removal area. If a saw cut would fall within 30 inches of a construction joint, cold joint, expansion joint, or edge, the concrete shall be removed and replaced to the joint or edge. Concrete sidewalk and/or driveway may be removed so that a minimum of 30-inch square is replaced. If the saw cut would fall within 12 inches of a score mark, the concrete shall be removed and replaced to the score mark.

701.8.2 Existing bituminous pavement removed in connection with construction shall be cut with a saw, pavement breaker, cutting wheel, or other suitable tool approved by the ENGINEER. Care shall be taken to assure that the edge of the removed pavement does not vary from a straight line more than 2 inches from the mean.

701.8.3 Saw cutting shall be 1-1/2 inches in depth or 1/4 the thickness of the pavement, sidewalk, or driveway, whichever is greater. All saw cuts or other scoring shall be made perpendicular to the surface of the material to be cut.

701.8.4 Any unnecessarily irregular breakage or cracking caused by the CONTRACTOR shall be removed and replaced by the CONTRACTOR without added expense to the OWNER.

701.8.5 The CONTRACTOR shall be responsible for the disposal of removed materials.

701.8.6 Saw cutting is required on all concrete or asphalt paving on State maintained streets or roads.

701.8.7 Paving cuts for manholes and valve boxes and other utility appurtenances shall be square and at dimensions specified on the Standard Detail Drawings or on the construction plans.

701.9 MAXIMUM LENGTH OF OPEN TRENCH

In developed areas, no more than 300 feet of trench shall be opened in advance of pipe laying operations. This distance may

be reduced due to traffic control considerations. Backfilling shall begin as soon as pipe is laid and inspected and shall keep pace with the pipe laying. In advance of trenching operations in undeveloped areas, the CONTRACTOR shall submit in writing or on plans for the ENGINEER'S approval, the maximum length of trench that will be open at any one time. Except by permission of the ENGINEER, the maximum length of open trench in any one location where concrete structures are cast in place will be that which is necessary to permit uninterrupted progress. Construction shall be pursued as follows: excavation, formwork, and setting of reinforcing steel, placing of floor slab, walls, and cover slab or arch shall follow each other without any one of these operations preceding the next nearest operation by more than 200 feet. Failure by the CONTRACTOR to comply with the limitations specified herein or as may be specifically authorized by the ENGINEER may result in a written order from the ENGINEER to halt progress of the work until such time as compliance with this paragraph has been achieved and the work can be proceeded in an orderly sequence of operations.

701.10 WIDTH OF TRENCHES

Trench widths will vary according to the type of pipe used, size of pipe, depth of trench, and soil conditions. The minimum width requirements, indicated below, are for proper laying, aligning and jointing of pipe as well as trench grading, bedding preparation, and backfilling.

701.10.1 TRENCH WIDTH FOR RIGID PIPE MATERIALS: Trench widths from bottom of pipe to a point 12 inches above the top of the pipe shall be kept to the practical minimum required for properly laying, aligning, grading, jointing, and backfilling of the pipe, but no less width than pipe outside diameter plus 16 inches. For stable soils which will stand a vertical cut, the maximum trench width at a point 12 inches above the top of pipe or at a point 5 feet above the bottom of the trench, whichever is less, shall be as follows:

701.10.1.1 The pipe outside diameter plus 2 feet for pipes 27 inches in diameter and smaller.

701.10.1.2 1.6 times the nominal diameter for pipes 30 inches in diameter or larger.

701.10.1.3 When soil will not stand vertical, the trench sides shall be sloped to provide not less than the outside diameter plus 16 inches at the pipe invert.

701.10.2 TRENCH WIDTH FOR NON-RIGID PIPES: The minimum clear width of the trench measured at the springline of the pipe should be 1 foot greater than the outside diameter of the pipe. The maximum clear width of the trench at a point 1 foot above the top of the pipe is equal to the

pipe outside diameter plus 2 feet. If the maximum recommended trench width must be exceeded or if the pipe is installed in a compacted embankment, then pipe embedment should be compacted to a point of at least 2-1/2 pipe diameters from the side of the pipe or to the trench walls.

701.11 ROCK EXCAVATION

701.11.1 Rock is defined as material which cannot be excavated without drilling and blasting. All stone or boulders less than 8 cubic feet in volume will be classified as earth; all larger boulders shall be classified as rock. If blasting is necessary to excavate such materials as shale, hardpan, soft sandstone, cemented gravel, or loose rock which normally can be classified as earth excavation, then this excavation shall be classified as rock excavation. Whenever a ledge of solid rock encountered with earth below it or where alternate layers of solid rock and earth occur, the earth shall be included in the allowance for rock when the thickness of the layer of earth is less than 12 inches, thus requiring it to be removed by blasting along with the ledges of rock. Blasting will be considered necessary when the soil and rock cannot be excavated at a rate of 50 cubic yards per hour by a competent operator with a back-hoe that has a minimum bucket curling force of 25,000 pounds (John Deere 690 or equivalent).

701.11.2 Whenever rock is encountered in the trench or elsewhere in any excavation required to be made, it shall be excavated to the line and grade as shown on the plans and within the limits described therein, unless otherwise authorized, in writing, by the ENGINEER.

701.11.3 For trenches, rock shall be excavated to a depth of 6 inches minimum below the outside bottom of the conduit except at points of rock and earth transitions at which points the rock shall be excavated to a minimum of 12 inches below the outside bottom of the conduit as shown on the detail sheets for trench cuts and backfill of rock. Any depression in the bottom of the trench caused by overshoot and/or excavating and being 6 inches or greater in depth from a theoretical bottom of trench grade shall be filled to the theoretical bottom of the trench with select soils. The trench shall be backfilled with select backfill material to a point 1 foot above the top of the conduit. The remainder of the trench shall be backfilled as specified herein. The complete trench backfill from the bottom through to the top of the subgrade shall meet the compaction and/or moisture requirements as specified herein.

701.11.4 BLASTING: Suitable weighted covering or mats shall be provided to confine all materials lifted by the blasting within the limits of the trench and to prevent injury of persons or damage

to property. Blasting shall be under the supervision of a person qualified and experienced in the use and handling of explosives. All blasting operations shall be done in accordance with applicable local, state, and federal laws, ordinances, and codes regulating the transportation, storage, and use of explosives. Forty-eight hours prior to blasting operations, the CONTRACTOR shall notify the New Mexico One Call Center, telephone 260-1990 and the Albuquerque Police Department.

701.12 FOUNDATION

701.12.1 All pipe shall be bedded on a stable foundation in a trench which is completely free of water. The ENGINEER shall determine the adequacy of the foundation. Class V soils shall not be used as a foundation. If Class V soils are encountered at the bottom of the trench it shall be removed to the depth authorized by the ENGINEER and replaced with Class I, II or III soils.

701.12.2 Where an unstable foundation condition is encountered, it must be stabilized before laying pipe or alternative foundation methods utilized. The CONTRACTOR will be paid for foundation stabilization when required by the ENGINEER. Failure to notify the ENGINEER of an obvious unstable foundation condition prior to proceeding with placement of the pipe shall result in complete removal of the affected pipe, foundation stabilization, and replacement of the pipe at the CONTRACTOR'S expense.

701.12.3 Should the trench be inadvertently over-excavated below the foundation, the area of over-excavation shall be filled with select material in 6 inch lifts and compacted to a density of not less than 95 percent of maximum density, as determined by ASTM D 1557.

701.12.4 Unless specifically approved in writing by the ENGINEER, the CONTRACTOR shall not proceed with pipe embedment in a trench where water is present or the foundation is saturated. Adequate dewatering, as specified in Section 701.7, shall be utilized.

701.13 PIPE EMBEDMENT

701.13.1 GENERAL:

701.13.1.1 The class of bedding used for each pipe shall be as shown on the plans or as specified in the Supplemental Technical Specifications.

701.13.1.2 The CONTRACTOR may request a change in the class of bedding required on a pipe, if authorized by the ENGINEER, all increase in the cost of labor and materials required to include upgrading of the pipe class will be at the CONTRACTOR'S expense with no additional cost to the OWNER.

701.13.2 RIGID PIPE EMBEDMENT:

701.13.2.1 The trenches shall be excavated in conformance with the trench width requirements in Section 701.10 and 701.5.

701.13.2.2 Embedment material shall be Class I, II, III, or IV soils, or lean fill as specified in Section 207.

701.13.2.3 All soil in the embedment zone shall be placed in lifts not exceeding 8 inches in uncompacted depth, except that material along the side of the pipe shall not be placed above the springline until the haunch area of the pipe is adequately filled and sliced such that no voids remain.

701.13.2.4 All soil shall be compacted to a density not less than 90 percent of maximum density, as determined by ASTM D 1557. The CONTRACTOR shall take care to assure that the pipe is not damaged or misaligned during compaction of the embedment.

701.13.3 FLEXIBLE PIPE EMBEDMENT:

701.13.3.1 Proper placement of soils in the embedment zone is extremely important in achieving a satisfactory installation of flexible pipe. The CONTRACTOR shall be aware that the soil classes have differing requirements relative to embedment. There are also differing requirements for embedment in dry and wet conditions (wet conditions meaning that the embedment zone will be subject to ground water).

701.13.3.2 Embedment material shall be Class I, II, or III soils, or lean fill as specified in Section 207.

701.13.3.3 Embedment soil shall be placed in lifts not exceeding 8 inches loose depth. The haunch shall be properly compacted by hand tampers utilizing due caution such that the pipe is not damaged or misaligned. Mechanical tampers shall not be utilized directly over the pipe in the embedment zone.

701.13.3.4 The CONTRACTOR may utilize acceptable on site soils in the embedment area which are in conformance with these specifications. The CONTRACTOR has the option of importing a different soil, however, additional compensation will only be allowed if the on site soils are Class IV or V.

701.13.3.5 Class I soil shall comply with the requirements of Section 302, AGGREGATE BASE COURSE.

701.13.3.6 Class II and III soils shall be compacted to a density of not less than 95 percent of maximum density in the embedment area, as determined by ASTM D 1557. The moisture content shall not exceed 5 percent above optimum.

701.14 FINAL BACKFILL

701.14.1 Final backfill shall consist of homogeneous soil except that boulders, frozen clumps, rubble, and Class V soils are excluded.

701.14.2 Final backfill shall be compacted to a density of not less than 90 percent of maximum density, as determined by ASTM D 1557 unless otherwise specified in the Contract Documents.

701.14.3 The upper portion of the final backfill may require specific soils and compaction in order to provide a suitable foundation for pavements, curb and gutter, sidewalk, or other type of structure.

701.15 COMPACTION METHODS

701.15.1 The CONTRACTOR shall be responsible for the compaction method utilized during foundation preparation, embedment placement, and final backfill except as otherwise specified herein or in the Supplemental Technical Specifications.

701.15.2 The use of mechanical vibratory compactors directly over the pipe is prohibited in the embedment area. Extreme care shall be taken when utilizing mechanical compactors in the haunch and initial backfill area in order to avoid damage to or misalignment of the pipe. The ENGINEER shall examine any damaged pipe and has the authority to direct that it be replaced with new pipe at no additional cost to the OWNER.

701.15.3 Flooding or jetting shall be allowed if the subsurface soils are compatible to its usage, as authorized by the ENGINEER. It shall not be used for compaction of flexible pipe, when the soil has a plastic limit of 7 or greater, and in areas of collapsible soils. The CONTRACTOR shall take any necessary precautions to minimize to negligible flotation of the pipe.

701.15.4 The CONTRACTOR shall, at the direction of the ENGINEER, excavate the compacted fill as necessary for the purpose of determining the adequacy of the compaction.

701.16 PAVEMENT

701.16.1 Either new street construction or pavement replacements shall satisfy the following design and construction requirements:

701.16.1.1 Unless permanent pavement is specified to be placed immediately, a temporary dust-free patch shall be placed wherever excavation is made through existing pavements, sidewalks, or driveways. The patch shall be placed, rolled, and maintained by the CONTRACTOR to provide a smooth surface for traffic until a permanent pavement is constructed within the time frame specified by the ENGINEER.

701.16.1.2 The subgrade preparation of the area to be paved shall be in accordance with Section 301 of these specifications. The asphalt pavement placed shall be in accordance with Section 336 and the concrete pavement shall be in accordance with Section 337. The placement of the other roadway items shall be in accordance with Section 340.

701.16.1.3 Material thickness for all pavement replacements within residential or arterial streets shall conform to the plans or the Standard Detail Drawings or match the existing pavement as authorized by the ENGINEER.

701.16.1.4 Pavement cuts of 8 ft. or more in width and 100 ft. or more in length shall be paved with a laydown machine.

701.16.1.5 When authorized by the ENGINEER, asphalt concrete base course may be used to replace surface course thickness requirements on streets that are scheduled for overlay.

701.16.1.6 The edges of all trenches at the base course level shall be neatly trimmed before beginning any paving replacement. All edges of the existing pavement adjacent to the trench cut shall be inspected. Undermined, broken, cracked, or unevenly cut portions shall be removed and the pavement edges retrimmed prior to pavement replacement. All vertical edges of the existing asphalt pavement adjacent to the trench cut and all surface areas for a width of at least 4 inches and no greater than 8 inches, shall be thoroughly cleaned and a tack coat applied prior to placing any hot mix asphalt. The finished surface of the pavement replacement shall be graded to conform to the existing contour both in cross section and profile.

701.16.1.7 Concrete pavement to replace cuts made in concrete paved streets, arterials, etc., shall conform to the Standard Detail Drawings for concrete pavement or in accordance with New Mexico State Highway Department requirements where applicable.

701.16.1.8 When more than one-half of the surface area of a manhole, lamphole or valve box is found to extend into the area to receive a permanent asphaltic hot-mix surfacing and/or base pavement replacement, the existing pavement surrounding the manhole, lamphole, or valve box shall be removed to within those limits which will permit a permanent pavement replacement to be made in accordance with the approved plans.

701.16.1.9 Asphaltic hot mix shall not be placed upon the concrete collar, nor shall traffic be permitted upon the collar for at least 24 hours, or longer, if so directed by the ENGINEER. A tack coat of asphaltic emulsion may be applied after the concrete has taken its final set. During this time adequate barricading of the area shall be maintained by the CONTRACTOR.

701.16.1.10 If in the course of a pavement removal, a manhole, lamphole, and/or valve box is encountered and has a concrete collar about it and the collar is performing adequately, no special construction need be made in the permanent pavement replacement.

701.16.1.11 The CONTRACTOR shall make any small grade or alignment adjustment of the manhole, lamphole, and/or valve box encountered that is necessary to provide a smooth riding surface between the existing pavement and the patch and/or within the patch itself.

701.16.1.12 TESTING

701.16.1.12.1 A sample of each type of soil encountered shall be classified in accordance with the requirements of ASTM D2487, and the moisture density relationship determined in accordance either ASTM D698 or D1557, whichever is applicable.

701.16.1.12.2 A compaction test shall be taken for each 2 feet depth per 200 feet trench length or less, as directed by the ENGINEER. Compaction tests shall be taken in accordance with ASTM D2922 and D3017. Areas represented by non-complying tests shall be reworked and re-tested for compliance.

701.17 MEASUREMENT AND PAYMENT

701.17.1 TRENCHING, BACKFILLING, AND COMPACTION:

701.17.1.1 Trenching, backfilling, and compaction shall be combined into one unit and shall be measured and paid for as follows:

701.17.1.2 Measurement shall be made along the centerline of the pipe.

701.17.1.3 The unit of measurement shall be by the linear foot per pipe diameter per specified increment of depth.

701.17.1.4 The following depth increments will apply:

701.17.1.4.1 For water line installations the costs for trenching, backfilling and compaction shall be included in the unit price per linear foot of pipe per pipe diameter for maximum depth, such as: 4 to 14 inch diameter at 6 feet, 16 to 24 inch diameter pipe at 7 feet and all pipe larger than 24 inch at 8 feet. Separate payment will be specified in the Bid Proposal when required depths exceed the above depths.

701.17.1.4.2 For sewer installations the increments shall be 8 feet or less, 8 feet to 12 feet, 12 feet to 16 feet, 16 feet to 20 feet and thereafter at 4 foot intervals.

701.17.1.4.3 All depths shall be measured to the nearest foot.

701.17.1.5 All depths shall be measured from the invert of the pipe to the top of existing ground elevation. The existing ground elevation shall be the elevation of the surface that exists along the centerline of the pipe at the time of construction staking for said trenching.

701.17.1.5.1 Whenever a special pipe embedment detail is specified, on the plans, the trench depth shall be measured from the bottom of the embedment to the top of existing ground elevation. However, no additional trench depth shall be measured as a result of inadvertent over-excavation nor to accommodate trench dewatering.

701.17.1.6 Payment will be made at the unit price per linear foot per diameter of pipe per depth increment as specified in the Bid Proposal, and will include trenching, backfilling, and compaction for all trench zones. No additional payment will be made for compacted materials to bring trench backfill up to required depth.

701.17.2 OVER-EXCAVATION: Required over-excavation for foundation stabilization shall be measured by the cubic yard of material removed and replaced with compacted suitable material. Payment will be made at the unit price per cubic yard of compacted replacement material and shall include excavation, backfill material, and compaction.

701.17.3 ROCK EXCAVATION: Rock excavation will be measured by the cubic yard within the specified limits of the trench configuration. Blasting will be included in the rock excavation. Payment will be made at the unit price per cubic yard.

701.17.4 UNSUITABLE MATERIALS: Removal and disposal of unsuitable materials from the construction site shall be measured by the cubic yard of excavated material. Payment will be made at the unit price per cubic yard of excavated material.

701.17.5 PAVEMENT, SIDEWALK, AND DRIVEWAYS: Removal and disposal of existing pavement, sidewalks, and driveways will be measured by the square yard or square foot whichever is apropos. Payment will be made at the unit price per square yard or square foot as specified in the Bid Proposal.

701.17.6 SELECT MATERIALS: Where selected material is required in the backfilling operations, the quantity of material will be measured by the cubic yard of compacted material in place in the trench. Payment will be made at the unit price per cubic yard of select material as indicated above.

701.17.6.1 Whenever a special pipe embedment detail is specified, measurement and payment shall be as identified in the Bid Proposal.

701.17.7 DEWATERING: Dewatering

operations for trench work shall be measured by the linear foot along the center-line of that portion of the trench which requires dewatering. Payment will be made at the unit price per linear foot of dewatered trench.

701.17.8 PAVEMENT:

701.17.8.1 Permanent or temporary pavement surfacing shall be measured and paid for in accordance with the paving section elements as defined under Section 300 for the specific item of work.

701.17.8.2 Permanent resurfacing or permanent surface patching will be measured on the basis of the square yard for new surfacing as provided in the applicable section of these specifications. For payment purposes, the normal maximum pavement cut width shall be as defined in the Table No. 701.17.8.2

TABLE No. 701.17.8.2
NORMAL MAXIMUM PAVEMENT CUT WIDTHS ALLOWED FOR PAYMENT PURPOSES

Soil Stability	Trench Depth (TD)	Pipe Size	Max. Pavement Cut Width
Stable. Soil stands in a vert. cut	Less than or equal to 5 feet	ND less than or equal to 27"	OD + 2 feet
"	Greater than 5'	ND less than or equal to 54"	TD + 2 feet
"	"	ND greater than 54"	1.6 X ND + TD + 3'
Unstable. Soil does not stand in vert. cut	Any	Any	2 X TD + OD

- NOTES: 1. TD is trench depth; ND is nominal pipe diameter; and OD is outside pipe diameter.
2. Individual locations or conditions may warrant greater cut widths than those specified above. The ENGINEER shall authorize in writing the increase in the above pavement cut widths.