



PLAN WITHOUT SIDEWALK (OR SIDEWALK SET BACK FROM CURB

CONSTRUCTION NOTES:

- A. FRAME 3 1/2" O.D. STEEL PIPE, COPE & WELD PIPE, GRIND SMOOTH.
- B. 2 1/2" O.D. STEEL PIPE COPE & WELD PIPE TO CHASSIS, GRIND SMOOTH.
- C. 16 ga. PERFORATED STEEL PANEL, RIVETS OR TEMPER PROOF SCREWS FASTENED AT 8"o.c. TO 1/2" x 1" CHANNEL.
- D. ROOF LINE ABOVE.
- E. (NOT USED)
- F. (NOT USED)
- G. 1/2" EXPANSION JOINT.
- H. TRASH RECEPTACLE (SEE STD. DWG. 2535.10).
- I. 4" SLAB WITH 4x4 - W4.0 WWF, USE 10' DEEP TURNDOWN AT PERIMETER, BROWN FINISH.
- J. EXISTING CURB (SHADED)
- K. MATCH SLOPE OF CURB.
- L. BENCH (SEE STD. DWG. 2535.09).
- M. THICKENED SLAB (TYP.)
- N. BUS STOP SIGN (TYP.)
- O. NEW CONCRETE INFILL IF SIDEWALK IS SET BACK FROM CURB. SIZE AND SHAPE OF INFILL MAY VARY.
- P. MATCH SIDEWALK WIDTH.

REVISIONS	CITY OF ALBUQUERQUE
	BUS SHELTER 'C' PLAN (W/O SIDEWALK)
	DWG. 2535.03 JANUARY 2003