



PLAN WITHOUT SIDEWALK (OR SIDEWALK SET BACK FROM CURB)

**CONSTRUCTION NOTES:**

- A. FRAME 3 1/2" O.D. STEEL PIPE, COPE & WELD PIPE, GRIND SMOOTH.
- B. 2 1/2" O.D. STEEL PIPE COPE & WELD PIPE TO CHASSIS, GRIND SMOOTH.
- C. 16 ga. PERFORATED STEEL PANEL, RIVETS OR TEMPER PROOF SCREWS FASTENED AT 8" o.c. TO 1/2" x 1" CHANNEL.
- D. ROOF LINE ABOVE.
- E. ROOF: HIGH STRENGTH F.R.P. SMOOTH SURFACE TOP AND BOTTOM. FASTEN TO 1/2" x 2" CHANNEL WITH RIVETS OR TAMPER PROOF SCREWS AT 8" o.c. PAINT TO MATCH SHELTER.
- F. BENCH (SEE DETAILS ON STD. DWG. 2535.09).
- G. 1/2" EXPANSION JOINT.
- H. TRASH RECEPTACLE (SEE STD. DWG. 2535.10).
- I. 4" SLAB WITH 4x4 - W4.0 WWF, USE 10' DEEP TURNDOWN AT PERIMETER, BROWN FINISH.
- J. EXISTING CURB. (SHADED).
- K. THICKENED SLAB. (TYP.)
- L. BUS STOP SIGN. (TYP.)
- M. NEW CONCRETE INFILL IF SIDEWALK IS SET BACK FROM CURB. SIZE AND SHAPE OF INFILL MAY VARY.
- N. MATCH SIDEWALK WIDTH.

| REVISIONS | CITY OF ALBUQUERQUE                |
|-----------|------------------------------------|
|           | BUS SHELTER 'D'<br>(W/O/ SIDEWALK) |
|           | DWG. 2535.05 JANUARY 2003          |